

LINE CONCENTRATOR NO. 2A  
SYSTEM TESTS

1. GENERAL

- 1.001 This addendum supplements Section 067-109-502.
- 1.002 It is issued to correct information contained in the note associated with Operational Test A4.

5. OPERATIONAL TESTS

The following changes apply to Part 5 of the section:

- (a) Test A4, Note following Step 8 - revised  
A4. Loop Around Test at Control Unit

STEP	ACTION	VERIFICATION
8	Manually operate S0/S1 relay.	1000 cycle tone heard.
	<i>Note:</i> The 1000 cycle tone heard in Step 8 is transmitted from the control unit over the trunk set up in Step 5 and looped back in the remote unit over the trunk selected in Step 3. Line 78 (TL01/TL11 jacks) is now connected to line 79 (TL00/TL10 jacks) through the remote unit. Transmission measuring equipment may be plugged into TL01/TL11 and TL00/TL10 jacks for transmission measurement. To release trunks set up on this call in order to make further loop around test call, consult Tests A and C. It is accomplished by making terminating test calls to idle lines not connected to trunks and selecting the two trunks used in Steps 1 through 8.	