

POWER SYSTEMS
EQUIPMENT TEST LIST
FOR
POWER PLANTS
LOCATED ON CUSTOMER OR TELEPHONE CO PREMISES

SEE SECTION 010-300-011 FOR EQUIPMENT TEST LIST INSTRUCTION.

EQUIPMENT TEST LIST						
B.S.P.	I S S	TEST OR REQT.	EQUIPMENT AND WORK DESCRIPTION	CLASS	FREQ.	JOB NO.
167-208-301	1		102G J86802 POWER PLANT			
		3.09	Boost Charge	MW	12M	
		4.01	Float Voltage	MW	M	
		4.02	Check Fuse Alarm	MW	12M	
		4.03	Check HLV Alarm	MW	12M	
167-210-301	5		105D J86446 POWER PLANT			
		3.13	Calibrate Voltmeter Relay	MW	12M	
		4.04	Check Float Voltage	MW	M	
		4.05	Check CEMF Operation Where Used	MW	3M	
		4.06	Check Low-Voltage Alarm	MW	12M	
		4.07-	Check TD Relay Operation	MW	12M	
		4.09	Where Used			
		4.10	Check High-Voltage Alarm	MW	12M	
		4.11	Check Discharge Fuse Alarm	MW	12M	
167-210-302	3		105E J86814 POWER PLANT			
		4.02	Check Fuse Alarm	MW	12M	
		4.03	Check Float Voltage Alarm	MW	12M	
		4.04	Check Float Voltage	MW	M	
167-215-301	7		110A AND 110B PLANTS J86572 AND J86455			
		4.02	Check Condition of KS-7105 Grid Battery	MW	6M	
		4.03	Check Panel Voltmeter	MW	12M	
		4.04	Check Regulator Float Voltage Adjustment	MW	M	
		4.05	Check Regulator Charge Voltage Adjustment	MW	M	
		4.06	Check Transfer of Load	MW	3M	
		4.07	Check for Regulation Tube Failure	MW	6M	
		4.08	Check for Power Failure Operation	MW	6M	
		4.09	Check for Rectifier Electron Tube Failure	MW	6M	
		4.10-	Check Discharge	MW	3M	
		4.12	Circuit Operation			
		4.13	Check Rectifier Fuse Alarm Operation	MW	12M	
		4.14	Check Discharge Fuse Alarm Operation	MW	12M	
		4.15	Check High-Low Voltage Alarm Operation	MW	12M	
		4.16	Check Regulation Alarm Operation	MW	12M	
			(110A 24-Volt Plant)			
		4.17	Check Indicating Alarm Operation	MW	12M	
			(110A 24-Volt Plant)			
167-217-301	7		111A POWER PLANT J86470			

