

**DYNAMIC OVERLOAD CONTROL CIRCUIT SD-27970-01**

**TESTS**

**NO. 1 CROSSBAR OFFICES**

*RR209, 0 LL  
Next to (Col-54)*

**1. GENERAL**

**1.01** This section provides a method of checking the dynamic overload control circuit (DOC) SD-27970-01 and route transfer in the associated switching entities.

**1.02** This issue affects the Equipment Test List.

**1.03** The tests covered are:

**A. Seizure, Route Transfer and Cross**

**Detection:** This test checks that: (1) the DOC will respond to a maximum of 30 incoming signals; (2) for each incoming signal the DOC will repeat identical signals to succeeding DOCs or to regional center; (3) signals will be sent to a maximum of 8 switching entities; (4) incoming signals are interrupted at a constant rate; (5) when a C lead becomes falsely grounded, an audible alarm and lamp indication will be originated at the associated switching entity.

**B. Timing:** This test checks that: (1) an incoming signal which persists for more than 31 to 38 seconds will be removed from all

associated switching entities, any succeeding DOC(s), and the traffic control circuit; (2) an alarm will be initiated at DOC under test.

**1.04** The tests require action and verification at traffic control circuit and switching entity (entities).

**1.05** Table A is provided to assist in associating RTC1\_ relay contacts with particular C\_ leads for a particular switching entity.

**2. APPARATUS**

**Test A**

**2.01** 893 cord, equipped with 411A tool and KS-6278 tool (for applying ground).

**All Tests**

**2.02** Blocking tools and insulators, as required. Use tools and apply as covered in Section 069-020-801.

**2.03** KS-3008 stopwatch or equivalent.

**3. METHOD**

STEP	ACTION	VERIFICATION
------	--------	--------------

**A. Seizure, Route Transfer, and Cross Detection**

**Seizure and Route Transfer**

1	At DOC— Block nonoperated RTC1_ relay associated with route under test.	
---	--	--

2	Request distant office to initiate overload signal on route under test.	
---	---	--

		At DOC— RTC_ relay associated with route under test operated for 29 seconds and released for 800 milliseconds for duration of overload signal. At traffic control circuit—
--	--	--

SECTION 216-262-501

STEP	ACTION	VERIFICATION
		ACK_ lamp associated with route under test lighted.
3	At RTC1_ relay associated with route under test— Insulate make contacts associated with all equipped switching entities except one under test. See Table A.	
4	At switching entity under test— Block nonoperated RT_ relay associated with route under test.	
5	At DOC— Remove blocking tool from RTC1_ relay associated with route under test.	At switching entity under test— RTCA_ lamp associated with route under test lighted. RT_ relay associated with route under test energized.
6	At DOC— Block nonoperated RTC1_ relay associated with route under test.	At switching entity under test— RTCA_ lamp associated with route under test extinguished. RT_ relay associated with route under test de-energized.

**Cross Detection**

7	Using 893 cord, momentarily apply ground to C lead of route under test to switching entity under test.  <i>Note:</i> Use Table A for identification of C lead to particular switching entity.	At switching entity under test— RTCA_ lamp momentarily lighted. RTCX lamp lighted. Major alarm sounded.
8	At switching entity under test— Operate RT-AR key.	RTCX lamp extinguished. Major alarm silenced.
9	Remove blocking tool placed in Step 4.	

TABLE A

SWITCHING ENTITY	FIRST	SECOND	THIRD	FOURTH	FIFTH	SIXTH	SEVENTH	EIGHTH
RTC1 Contact	11	10	9	7	4	3	2	1
RTC1 C-- Leads	00 - 29							

STEP	ACTION	VERIFICATION
10	At traffic control circuit— Discontinue overload signal on route under test.	
11	Repeat Steps 1 through 10 for each remaining route to switching entity under test.	
12	Repeat Steps 1 through 11 for each remaining switching entity to be tested.	
13	Remove insulators placed in Step 3.	
14	Remove blocking tool placed in Step 6.	
<b>B. Timing</b>		
1	At DOC— Insulate 10B of TM_ relay associated with route under test.	
2	Block operated RTC1_ relay associated with route under test; <i>start timing.</i>	In 31 to 38 seconds— TM_ relay associated with route under test operated. <i>Restart timing.</i> In 13 to 32 seconds— DOC lamp lighted. Major alarm sounds.
3	Remove blocking tool from RTC1_ relay associated with route under test.	
4	Operate DOC-AR key.	DOC lamp extinguished. Major alarm silenced.
5	Remove insulator from TM_ relay of route under test.	
6	Repeat Steps 1 through 5 for each remaining equipped route to be tested.	