

HOLIDAY RECORDING TRUNKS  
ROUTE TRANSFER TESTS  
USING MASTER TEST FRAME  
NO. 5 CROSSBAR OFFICES

1. GENERAL

1.01 This section describes a method of making tests of route transfer to holiday recording trunks using the master test frame in No. 5 Crossbar Offices.

1.02 Before making these tests discuss with Traffic and agree to the:

- Time of day to make the tests.
- Correct announcement to be recorded.
- Adequacy of the Routing Sketch, Marker Cross-Connection, and Route Transfer.

2. TEST PROCEDURE

2.01 If required, patch the recording equipment to the trunk equipment.

2.02 Remove busy from holiday recording trunk equipment.

2.03 Put busy plug in route transfer jack operating route transfer relays for holiday recording in markers.

2.04 Use the master test frame to make a route advance test.

- Test the route advance functions of each completing marker (Section 218-122-501).
- Test each holiday recording trunk for proper operation (Section 218-264-501).

*Note:* See the route transfer sketch and other cross-connection records as required.

2.05 When tests are complete:

1. Remove busy plug from the route transfer jack.
2. Make the holiday recording trunk equipment busy.
3. Remove any patch cords placed in 2.01.