

DYNAMIC OVERLOAD CONTROL CIRCUIT ES-27742-01

TESTS

NO. 5 CROSSBAR OFFICES

1. GENERAL

1.01 This test checks that the dynamic overload control circuit in a No. 5 crossbar office will respond to a traffic overload signal received from the regional center to provide alternate route cancellation and/or to make busy all or part of the trunks between the regional center and the No. 5 crossbar office.

1.02 This section is reissued for the following reason:

- (a) To add test B for checking the optional use of the DOC (Dynamic Overload Control) in a No. 5 crossbar office arranged for EADAS/NM (Engineering Administration Data Acquisition System Network Management).

This reissue affects the Equipment Test Lists.

1.03 The tests covered are:

A. *Response to Traffic Overload Signal From Regional Center:* This test checks that the dynamic overload control circuit in a No. 5 crossbar office will respond to a traffic overload signal received from the regional center and provide alternate route cancellation and/or make-busy all or part of the trunks between the regional center and No. 5 crossbar office.

B. *Response to Traffic Overload Signal From EADAS/NM Center:* This test checks that the EADAS/NM may at times request to take over from the dynamic overload control, the control of route transfers.

1.04 Reference to SD-25762-01, Note 402, MTF jack, lamp, and key circuit, and visual

inspection of punchings involved will determine how route transfer is controlled.

- (a) Exclusively via the DOC circuit
- (b) Exclusively via the EADAS/NM interface
- (c) Either via DOC or via EADAS/NM.

1.05 If more than ten route transfer relays are provided, the TR2, TR3, TR4 are also provided and will operate from the TR1 relay in Step 12.♦

1.06 Test A requires action and verification at the regional center; jack, lamp, and key circuit; trunk make-busy circuit; and dynamic overload control circuit.

1.07 ♦Test B requires action and verification at EADAS/NM central unit; jack, lamp, and key circuit; and dynamic overload control circuit.♦

1.08 *Lettered Steps:* A letter, a, b, c, etc, added to a step number in Part 3 or 4 of this section indicates an action which may or may not be required depending on local conditions. The condition under which a lettered step or a series of lettered steps should be made is given in the ACTION column, and all steps governed by the same condition are designated by the same letter within a test. Where a condition does not apply, all steps designated by that letter should be omitted.

2. APPARATUS

Test A and B

2.01 Blocking tools as required. Use tools and apply as covered in Section 069-020-801.

NOTICE

Not for use or disclosure outside the
Bell System except under written agreement

3. METHOD

STEP	ACTION	VERIFICATION
A. Response to Traffic Overload Signal From Regional Center		
1	Establish talking connection to regional center.	
2a	If option Z is provided— At trunk make-busy circuit— Block nonoperated TB relays associated with dynamic overload control circuit.	
3b	If option Y is provided— At jack, lamp, and key circuit— Block nonoperated RT_ relays associated with dynamic overload control circuit.	
4	Request regional center to transmit traffic overload signal.	At dynamic overload control circuit— S relay operated. SA relay operated momentarily SR relay operated. If option Z is provided— At trunk make-busy circuit— TB relays energized. If option Y is provided— At jack, lamp, and key circuit— RT_ relays energized. At regional center— Signal returned to regional center via telegraph send loop.
5	Request regional center to remove traffic overload signal.	At dynamic overload control circuit— S relay released. SR relay released. If option Z is provided— At trunk make-busy circuit— TB relays de-energized. If option Y is provided— At jack, lamp, and key circuit— RT_ relays de-energized.
6a	If option Z is provided— At trunk make-busy circuit— Remove blocking tools from TB relays.	
7b	If option Y is provided— At jack, lamp, and key circuit— Remove blocking tools from RT_ relays.	
8	Release talking connection to regional center.	

STEP	ACTION	VERIFICATION
B.	Response to Traffic Overload Signal From EADAS/NM Center	
1	Establish talking connection to EADAS/NM central unit.	
2	At MTF— Operate RTF key.	
	Note: If route transfer is controlled either via DOC or EADAS/NM, operation of RTF key is required. If control is exclusively via EADAS/NM, operation of RTF key is not required. Refer to paragraph 1.04.	
3	Block nonoperated RT_ relays associated with EADAS/NM control.	
4	Request the EADAS/NM center to enable control of route transfer relays.	At MTF— TR1 relay operates.
		Note: TR2, TR3, and TR4 relays operate if provided.
		At EADAS/NM central unit— Discrete on indication received indicating that EADAS/NM has control of route transfer.
5	Request the EADAS/NM center to enable controls for the operation of route transfer relays.	At MTF— RT_ relays energized.
6	Request the EADAS/NM center to disable controls for the operation of route transfer relays.	RT_ relays de-energized.
7	Remove blocking tools from RT_ relays.	
8	Release talking connection to EADAS/NM center.	