

OUTGOING TRUNK CIRCUITS
OPERATION TEST
USING TEST AND LINE VERIFICATION TEST CIRCUIT SD-32379-01
STEP-BY-STEP OFFICES ARRANGED FOR ANI-TYPE C

1. GENERAL

1.001 This addendum supplements Section 227-575-500, Issue 1.

4. METHOD

The following change applies to Part 4 of the section.

- (a) Test C, Step 14 — revised Verification to read as follows:

Upon completion of successful test —
AT lamp extinguished.
CL-, TTO, OS, OPR, TP, FRG, L, TNK,
TOF, IDC, ST-, ST10 lamps lighted.
Test tip-party directory number displayed.