

DIMENSION® 2000 AND CUSTOM PBX
(CSS 201L)
X-RAY TEST 20
(PARK TAPE)

1. GENERAL INFORMATION
 2. RECORDS
 3. TEST EQUIPMENT
 4. TEST PROCEDURES
 5. MINIMUM CIRCUIT PACK REQUIREMENTS
-

1. GENERAL INFORMATION

1.1 Description

- 1.11 This section describes the procedures to be followed to perform X-Ray Test 20.
- 1.12 X-Ray Test 20 clears the network and attendant consoles and parks the tape between the beginning of tape and load point marks.

2. RECORDS

- 2.1 Form SD-97-1313 is required for recording the results of this test.

3. EQUIPMENT

- 3.1 Test Sets - See Section 400 of Handbook 281.

4. TEST PROCEDURES

4.1 Preliminary

- 4.1.1 This test should always be performed before the x-ray tape is removed from the mini-recorder.

PRIVATE

THE INFORMATION CONTAINED HEREIN SHOULD NOT BE DISCLOSED TO UNAUTHORIZED PERSONS. IT IS MEANT SOLELY FOR USE BY AUTHORIZED BELL SYSTEM EMPLOYEES.

4. TEST PROCEDURES (Cont'd)

4.2 Test Execution

4.2.1 To execute X-Ray Test 20, momentarily operate the EXECUTE, 2, 0 keys at the MAAP.

4.3 Test Pass Indication

4.3.1 The MAAP will display fault code 620 and the BUSY-OUT will flash when the tape is in park position.

4.4 This completes the x-ray testing per X-Ray Test 20.

5. MINIMUM CIRCUIT PACK REQUIREMENTS

5.1 The system should be equipped per the COD for this test.

Reason for Issue:

New Section

Manager, Denver PBX PECC