

TYPE N2 CARRIER TELEPHONE SYSTEM
OVER-ALL SYSTEM
INITIAL LINE-UP AND MAINTENANCE TESTS

1. GENERAL

1.01 This section covers the operating instructions for initial and maintenance tests on the terminal equipment and high-frequency line of the N2 carrier telephone system.

1.02 The information in this section is intended to be used after the terminal and repeater equipment has been installed and the equipment and line facilities are ready for the tests and adjustments preparatory to placing the carrier system in service. The information also applies to the operation and maintenance of the system while it is in service.

1.03 The extended application of direct distance dialing and the related signaling equipment emphasize the necessity for closely following operating procedures which reduce to a minimum the number of circuit interruptions and irregularities which affect the operation of the signaling equipment. The necessity of applying test and operating procedures without omitting any steps is important in order to avoid irregularities which are likely to result from the use of abbreviated or unauthorized procedures.

1.04 Where direct distance dialing is in operation on the trunks working over a system, it is necessary that precautions be taken to avoid false operation of switching equipment, cutoffs, and wrong numbers. When a system or a channel is taken out of service, the associated trunks should be made busy to traffic at the secondary testboard, or its equivalent, at each end of the trunk.

Note: Caution should be exercised to avoid causing hits on systems carrying SAGE, data, or telegraph transmissions.

1.05 *Testing and switching apparatus should be calibrated and maintained in accordance with standard instructions as outlined in Bell System Practices. The calibration of testing*

apparatus is important since failure to meet test requirements may be due to errors caused by defective testing apparatus. Testing apparatus should be calibrated at such intervals as is necessary to insure accuracy of measurement.

2. INITIAL TESTS

2.01 Initial tests include those tests which are made on the cable facilities, testing apparatus, power supply, order wires, and alarm circuits to determine that all facilities will meet their individual requirements prior to the system line-up procedure.

2.02 Details regarding initial tests are not included in this section, but should be covered by instructions applying to the specific project and prepared by the operating company. Initial tests may include such items as follows:

(a) **Cable Tests:** Tests of resistance, resistance unbalance, tests for conductor turnover, crosstalk, high-frequency attenuation, and noise measurements, on the cable facilities.

(b) **Testing Apparatus:** Tests and calibrations as recommended for the various test sets as covered in the Bell System Practices.

(c) **Power Supply:** Tests of power supplies at terminal and repeater power supply points.

(d) **Order Wire and Alarm Circuits:** After the order wire and alarm circuits at the terminals and repeaters have been connected to the line conductors and adjusted in accordance with circuit information, initial tests should be made of transmission and signaling features of the order wire. Operations associated with the alarm circuit should be checked to insure that the alarms are properly received at each of the stations where receiving equipment is located.

SECTION 362-800-300

2.03 The following initial steps should be taken to reduce delays in line-up procedures:

(a) Circuit layout or equivalent information should be available showing the following data:

- (1) Cable pair assignments
 - (2) Span pad values
 - (3) Voltage and resistor values at dc power supply points
 - (4) Type of repeater, L-H or H-L, N1, N1A or N2
 - (5) Repeater slope adjustments
 - (6) Design noise requirement if other than the standard requirement
- (b) Repeater mounting brackets should be in place and the span pads should be wired to the cable terminals or in cross-connecting cabinets, as required.

(c) Check should be made to verify that the cable protector blocks are in place and that heat coils are removed and strapped out of terminals arranged for heat coils. System line-up and application to service should be carried out as called for in system and circuit order information in accordance with instructions in this subdivision.

3. MAINTENANCE TESTS

3.01 Periodic tests are made on the terminal and high-frequency line to detect apparatus which has developed trouble or has aged to the point where, if it remained in service, it might cause impairment to service, as well as to indicate variations in the high-frequency line which need corrective measures. These tests are covered in the appropriate subdivisions in this division of practices.