

TYPE N3 CARRIER TELEPHONE SYSTEM
TERMINAL EQUIPMENT
POWER SUPPLY UNIT
TESTS AND ADJUSTMENTS

1. GENERAL

1.001 This addendum supplements Section 362-903-501, Issue 3. Place this pink sheet ahead of Page 1 of the section.

1.002 This addendum is issued to change the test points for making the In-Service Output Ripple Voltage Test. This addendum affects the Equipment Test List.

2. CHANGES TO SECTION

2.001 On the bottom of Page 1, delete the copyright notice and add the following:
Not for use or disclosure outside the Bell System except under written agreement.

2.002 On Page 4, revise Step 1 as follows; retain the note following Step 1.

At the N3 switching set, connect the VTVM test cord red lead to -21V and the black lead to G.

Requirement: 0 to 0.012 volt.

NOTICE

Not for use or disclosure outside the
Bell System except under written agreement