

DIGITAL TRANSMISSION SYSTEMS

T1 DIGITAL LINE

INSTALLATION AND INITIAL LINEUP TESTS

1. GENERAL

1.01 This section lists the installation and initial lineup tests for the T1 digital line and associated equipment.

1.02 This section is reissued to delete Table B which contained a list of routine maintenance tests and to add some listings to Table A (indicated

by shaded areas). The tests that were listed in Table B are given in the Equipment Test List.

1.03 Table A includes references to the section in which each test or adjustment is described. All tests in Table A should be made during initial lineup.

TABLE A
INSTALLATION AND LINEUP TESTS

TEST	SECTION
Pair-Loss Measurements	365-211-516
Preinstallation Test for 201-, 205-, 208-, and 300-Type Repeaters	365-221-500
Installation and Replacement of Office Repeaters	365-222-200
Span Line Powering	365-223-500
Overall Line Tests	365-224-500
Order-Wire Facilities	365-320-300
J98713F Line Terminating Unit	365-300-203