

LINE JUNCTOR REDISTRIBUTION
6IL-6LCC to 9IL-9LCC

CONTENTS

- 1. GENERAL
- 2. PREPARATION FOR ROUTINE OF INCOMING TRUNKS
- 3. STEP NO. 1 TERM. MARKER
- 4. STEP NO. 2 LINE JUNCTOR CONNECTOR FRAME
- 5. STEP NO. 3 LINE JUNCTOR GROUPING FRAME
- 6. STEP NO. 4 TIP RING AND SLEEVE TEST
- 7. CLEAN-UP WORK

1. GENERAL

1.1 This section covers the redistribution of line junctors.

From:
ED-25713-10, Chart 5, 6IL & 6LCC with
90 junctors per HC

To:
ED-25713-10, Chart 8, 9IL & 9LCC with
100 junctors per HC

2. PREPARATION FOR ROUTINE OF INCOMING TRUNKS

2.1 Preparation for routine of incoming trunks are made as specified in Handbook 40, Section 90, Paragraph 3.

2.2 Paragraph 3.4 of Section 90 refers to temporary cross connections in the term. marker.

2.21 These cross connections are as follows;

JR6 to JGA6
 JGE6
JR7 to JGA7
 JGE7
JR8 to JGA8
 JGE8

2.3 No cross-connections are to be removed. The cross connections specified in Paragraph 2.21 are to be installed over the existing connections.

3. STEP NO. 1 TERM. MARKER

3.1 Remove each marker from service and block to use 1st subgroup junctors only, per SD-2511-01, Table 11, for 6 incoming frames.

3.2 Remove the temporary cross connections installed under Paragraph 2.21.

3.3 Change the present cross connections per T-25283-55 to agree with T-25283-40.

3.4 At the completion of Paragraph 3.3 on each marker, block to use 1st subgroup per SD-25511-01, Table 11, for 9 incoming frames and return to service.

4. STEP NO. 2 LINE JUNCTOR CONNECTOR FRAME

4.1 Change the M-J straps of the LJA & LJB terminal strips per Figure 1.

Line Choice Number	0	1	2	3	4	5	6	7	8	9
From T-25275-18		Fig 2	Fig 14	Fig 14	Fig 15	Fig 15				
To T-25275-18		Fig 3	Fig 3	Fig 3	Fig 3	Fig 3				

FIG. 1 MODIFICATION OF M AND J STRAPS
(Par. 4.1)

5. STEP NO. 3 LINE JUNCTOR GROUPING FRAME

5.1 Disconnect all cross connections except those shown in Figure 2.

LINE CHOICE	FRAME	CHAN- NEL	8	7	6	5	4	3	2	1	0
9A 9B	9	0				5R 5L	4R 4L	3R 3L	2R 2L	1R 1L	OR OL
9A 9B	9	1				4R 4L		2R 2L		OR OL	

FIG. 2 REUSED CROSS CONNECTIONS
(Par. 5.1)

5.2 Connect 240 1st subgroup junctors (cabled junctors)

5.3 Connect the cross connection not connected in the preliminary work. There are 162 junctors to be cross-connected as specified on ED-25713-10, Chart 8.

6. STEP NO. 4 TIP RING AND SLEEVE TEST

6.1 Buzz test the T, and R of all junctors established under Paragraph 5.2 and 5.3.

6.2 Remove a marker from service and use this marker and the TTI to check the sleeve of all 1st subgroup junctors.

6.3 Block this marker, per SD-25511-01, Table 11 to use 2nd subgroup junctors only for 9 I, and use the marker and the TTI to check the sleeves of all 2nd subgroup junctors.

6.4 Remove the blocks from all the markers, and after making any necessary check, restore them to service.

7. CLEAN-UP WORK

7.1 The markers and junctors are now operating in the standard manner for the 9 I - 9 LCC distribution and the incoming trunks in frames 6, 7 and 8 may now be loaded.

7.2 The JPL relay per SD-25511-01, shall be removed as there is no longer any use for it.

No arrows are shown due to extensive changes.

R. E. RAHMES

Engineer of Installation

Reason for Reissue:
Complete handbook revision.

Replaces Section 42C15 dated 6-19-47.