

WIDEBAND REMOTE SWITCH OFFICE TESTS

CONTENTS

1. GENERAL

2. TEST INDEX

1. GENERAL

1.1 This section provides the tests of the Wideband Remote Switch and its associated circuits.

- SD-27900-01 WB Remote Switch Circuit
- SD-27909-01 VSS Supply Circuit
- SD-27930-01 WB Remote Switch Terminating Test Line Circuit

1.2 The Remote Switch circuit can be located in a No. 5, No. 1, or Tandem Crossbar office, Panel, Toll, or Step X Step office.

1.3 Section 801F requires a man in the control office and one in the remote office with a communication link between them.

1.4 Section 801G requires that the control office is ready to switch Remote Switch calls.

2. TEST INDEX

2.1 Table A lists the test sections in the order that they should be applied.

TABLE A

Section	Title
801A	Video Supervisory Signal Supply Circuit Tests (SD-27909-01)
801B	VSS Circuit Adjustment Procedures
801C	Trouble Detecting Procedure for the VSS Circuit (SD-27909-01)
801D	Wideband Remote Switch Terminating Test Line
801E	Wideband Remote Switch Crosspoint
801F	Remote Switch Control Lead Verification
801G	Remote Switch Call Through Tests using the Priming Set
801H	Priming Set Priming Information

Manager, Crossbar Product Engineering
 Control Center