

INDEX OF TESTS
 LINE LINK FRAME

1. GENERAL INFORMATION

1.1 This section with Sections 2A and 2B list the tests to be applied to line link equipment and also lists the performance requirements for line link equipment in No. 1 Crossbar Offices. Test method details are contained in the separate sections listed herein and the test sets required for each test operation are shown. Cords and accessories are not listed, reference shall be made to detailed methods for these items.

1.2 Test Planning and Control: Refer to Section 0 for information required prior to planning or conducting job test operations.

1.3 The notes referred to in the "SEE NOTES" column of Sections 2A and 2B are listed below.

1.4 Sequence of Tests: Due to the variety of local job conditions and procedures no positive and definite sequence for performing all the tests contained in sections of this series, which would be applicable to each job, is prescribed. However, it is recommended that, in general, the tests should be applied in the order indicated by the

arrangement of tests in Sections 2A and 2B. Where feasible, and with due regard to prescribed intervals and cycles, supplementary tests (except those which are performed as a part of routine tests) should be performed before routine tests. When there is a preferred sequence to be followed in performing the tests contained in individual sections, this sequence is indicated in the general information paragraph of the section or the arrangement of the methods information.

2. REQUIREMENTS

2.1 Tests listed in this summary conform to the requirements of BSP 634.001 Performance Requirements Section for No. 1 Crossbar Offices.

3. SUPPLEMENTARY TESTS

3.1 Sections 2A and 2B list all the supplementary tests required on line link equipment.

4. ROUTINE TESTS

4.1 Table 1 shows the routine requirements which the equipment is to meet. Section 2B lists the information necessary for making the tests.

TABLE 1

| | Routine No. | Frequency | | Performance % Failure | Last No. of Cycles | Avg. No. Cycles Req'd | Test Set Req'd | Test Methods | |
|----------------------|-------------|-----------|------|-----------------------|--------------------|-----------------------|----------------|--------------|-------|
| | | Min. | Max. | | | | | Sect. | Para. |
| Line Link Controller | 2701 | 1-3 | 1-1 | Clear | 2 | 12 | ITE-4032 | 102 | 6 |

NOTE 1: This routine test need not be continued during the concentrated load test interval.

R. E. RAHMES
 Engineer of Installation

Reason for Reissue:
 To renumber section and general revision.

Replaces Section 0.1 dated 1-18-51.