

FIRST CLASS MAIL

Installation Engineering Handbook 62
(File Ahead of Section 207)
Temporary Instruction
Western Electric Company, Incorporated
Columbus Works

Section T.I. - 207
12-9-69

TEST OF MISCELLANEOUS INCOMING TRUNKS

1. GENERAL

1.1 This temporary instruction is issued to provide information on test results after the Flash Removal Program has been completed in a No. 1 Crossbar Office and its connecting offices.

2. INSTRUCTION

2.1 When any test result specifies that either 60 and/or 120 IFM Flash is to be verified, the corresponding 60 and/or 120 IFM Tone is to be verified.

Manager, Crossbar Product Engineering
Control Center