

TOLL TYPE EQUIPMENT TEST LIST
TEST CENTER OPERATION

1. GENERAL

1.01.1 This addendum is issued to supplement the main section for application in the Southwestern Company.

1.01.2 Trunks connected to automatic test frames shall be scheduled for overall 1000 Hz loss measurements as provided in

equipment test list Section 660-001-011, Issue 3.

1.01.3 Trunks that are to be measured manually shall be scheduled for overall 1000 Hz loss measurements as provided in addendum 660-402-300 SW.

1.01.4 The following ETL shall be used to schedule 1000 Hz loss measurements only on trunks that are to be measured manually.



<u>B.S.P.</u>	<u>ISS</u>	<u>Test of Reqt.</u>	<u>EQUIPMENT and WORK DESCRIPTION</u>	<u>Class</u>	<u>Freq.</u>	<u>Job No.</u>
660-402-300SW	A		Transmission Maintenance - overall 1000 Hz Loss Measurements on Message Trunks:			
			Trunks containing a carrier channel or equipped with other than "E" type repeaters	MW	3M	
			Trunks equipped with "E" type repeaters	MW	6M	
			Trunks with outside plant facilities not equipped with a gain device	MW	12M	