

NO. 5 CROSSBAR
AUTOMATIC CALL DISTRIBUTOR SYSTEM, PHASE I
BALANCE PROCEDURES
DROP BUILD-OUT CAPACITOR (DBOC) SELECTION AND VERIFICATION

1. GENERAL

1.001 This addendum supplements Section 660-477-502, Issue 1. Place this pink sheet ahead of Page 1 of the section.

1.002 This addendum is issued to change the terminations used in 4-wire terminating sets.

2. CHANGES TO SECTION

2.01 The terminations in the 4-wire ports of the terminating sets shown in Fig. 12, 14A, 14B, 16, 17 and 20 must be changed from 900 ohms to 600 ohms. If this is not done, the requirements stated in Section 660-477-301 cannot be met.

NOTICE

Not for use or disclosure outside the
Bell System except under written agreement