

**LINE INSULATION TEST FRAME
EQUIPMENT DESIGN REQUIREMENTS
NO. 1 CROSSBAR SYSTEM**

1. GENERAL

Under J23651B

1.001 This addendum supplements Section 816-602-150, Issue 4.

Add: To List 1

1.002 This addendum is issued:

- (a) To provide line insulation test failure printouts by directory number on the LIT teletypewriter.
- (b) To provide an LIT teletypewriter printout of skip resistor assignments.

Calling Line Reg No.,
Fig. 19
Vertical File Aux,
Fig. 20

WIRE EQUIP NOTES

1 0

1 0

The above changes are in accordance with SD-25947-01, Issue 16B.

Add:

4. EQUIPMENT

The following changes apply to Part 4 of this section:

- (a) J23651B, List 1—revised.
- (b) J23651B, List 18 and List 19—added.

List 18 — Equipment and wiring per SD-25947-01, Fig. 19 and option ZY required in addition to first list 5 (circuits 0 through 3) to provide for LIT failure printouts by directory number on the LIT teletypewriter.

List 19 — Equipment and wiring per SD-25947-01, Fig. 20 required in addition to list 1 to provide an LIT teletypewriter printout of skip resistor assignments.

Bell Telephone Laboratories, Incorporated

Dept 5245

NOTICE

Not for use or disclosure outside the
Bell System except under written agreement