

MANUAL TEST OF MACHINE RINGING INCOMING TRUNKS
FROM LOCAL MANUAL OFFICES
NO. 1 OFFICE

1. GENERAL

1.01 This addendum, which supplements Section A230,205, Issue 1, is issued in order to change the testing procedure in connection with machine ringing incoming trunks from local manual offices, for those offices provided with automatic testing facilities.

1.02 In those offices where the automatic test line and ringing test line circuits are provided, tests (a), (b), (c) and (d), described in this section, should be disregarded and the procedure for testing should be in accordance with Section A230,234. Tests (e), (f) and (g) should be continued in these offices, however, as a supplementary test.