

AT&T INSTALLATION REQUIREMENT CHANGE NOTIFICATION - ATT-TP-76300-002

TO: ALL AT&T INSTALLATION SUPPLIERS

Date: 04-23-07

EFFECTIVE DATE: 5 days from posted date or as per Supplier's Contract

Submitter's Name: Larry Wong

TP: TP76300 Subject: Ironwork Requirements Action: Add

Section: I

Section Title: IRONWORK

Subsection: 2

Section Title: REQUIREMENTS

Subsection: 2.6

Subsection Title: Frames, Bays, Battery Stands and Equipment

Prior to Change:

NONE

Post Change:

2.6.6 a) In lineups where 7'-0" or 9'-0" frames are the primary or only support for overhead cable rack, the equipment frame shall be secured to building floor with four anchors and junctioned to adjacent frames in accordance to paragraph 2.6.2. Cable rack shall not be considered a top support and cannot be relied upon to provide structural support of equipment frames.

Questions relative to this IRCN should be addressed to Laurie Gustin at 310-640-4220

Laurie Gustin

Project Manager Area Manager, NP&E

Enterprise Technology Support

Laurie.gustin@att.com

Access the TP's on the Extranet Site <https://ebiznet.sbc.com/sbcnebs>

Concurred

Senior Installation Manager-Network Quality, West

Date: 04-23-07

(Mike Sula)

Senior Installation Manager-Network Quality, Southwest

Date: 04-23-07

(Stan Gibson)

Senior Installation Manager-Network Quality, Midwest

Date: 04-23-07

(John Turrentine)

Area Manager Common Systems Ironwork

Date: 04-23-07

(Larry Wong)

Release Approved

Area Manager Enterprise Technology Support

Date: 04-23-07

(Mike Burghardt)