

Prepared by
The Pacific Telephone and Telegraph Company
Southern California Area

BELL SYSTEM PRACTICES
Outside Plant Construction
and Maintenance

ADDENDUM G50.225.1
Issue B, March, 1950-S
T. P. T. & T. Co.

CABLE TESTING - GENERAL

BREAKDOWN TEST SET - BO-240457

NOTES CONCERNING THIS ADDENDUM

This Addendum contains information relative to the use of the modified BO-240457 Test Set and additional information regarding precautionary measures to be followed.

The cross-reference "See Addendum" should be marked after Paragraphs 1.06 and 4.15 to indicate the addition of new information. Part 3 has been replaced and should be marked "See Section G50.225.2, Part 3."

1. GENERAL

1.07 When using the modified BO-240457 Test Set refer to Sections G50.225.2 and G86.060.2 for complete operating and maintenance instructions.

3. PRECAUTIONS

Note: The precautionary measures listed in Part 3 of Section G50.225.2 and Parts 3 and 4 of the addendum to G50.225.2 shall be followed when using the BO-240457 Test Set or the modified version of the BO-240457 Test Set.

5. RESTORING TEST PAIR TO NORMAL

5.01 Any circuits working on the pair should be restored to service and the subscriber notified in accordance with local routine. The Binding Post Caps and linen tags should be removed at the working appearances.

5.02 At terminations where the pair is not working, the Binding Post Caps may be left on the pair. Caution signs hung on poles at distribution terminals in which the pair appears should be removed.