Prepared by
The Pacific Telephone and Telegraph Company
Southern California Area

BELL SYSTEM PRACTICES
Outside Plant Construction
and Maintenance

ADDENDUM G50.637.5
Issue A, September, 1947-S

GENERAL CABLE SPLICING

STRAIGHT SPLICE IN B DISTRIBUTION CABLE

NOTES CONCERNING THIS ADDENDUM

This addendum supplements Section G50.637.5 with modifications in the tape wrapping procedure at splices of B Distribution Cable.

The cross-reference, "See Addendum", should be marked in Section G50.637.5 after paragraph 3.16 to indicate the addition of new instructions.

3. APPLYING SPLICE PROTECTION

3.17 Apply two half-lapped layers of friction tape over the outermost layer of B tape and paint thoroughly with No. 2 asphalt paint to which has been added 1/4 pound of aluminum powder per pint of paint.