

LASHED AERIAL CABLE

TWO OR MORE CABLES

NOTES CONCERNING THIS ADDENDUM

This addendum is being reissued so it will conform to Issue 3 of the main section. It provides instructions for placing temporary strand in accordance with local requirements and deletes reference to "sliding rings" which are not standard in this area.

"See Addendum" should be marked in G52.128.1 to indicate the following:

- Paragraph 3.02 - Modified
- Paragraph 4.01 - Replaced

3. EXISTING CABLE

- 3.02 Delete reference to "sliding rings."

4. REMOVAL OF ATTACHMENTS

4.01 Remove span clamps from the strand and temporarily support the drop wires at the pole providing that electrical and vertical clearances can be maintained in this manner. Where drop wires cannot be temporarily supported at the pole, or where there are numerous span clamps, a temporary strand may be placed between the poles above the level of the existing strand to provide a support for the span clamps providing the required vertical separations can be obtained. The temporary strand should be dead ended at each pole by the wrap method.

Note: DO NOT RIDE TEMPORARY STRAND. After lashing has been completed, transfer span clamps and remove the temporary strand.