

INCOMING VERIFICATION TRUNKS

1. GENERAL

1.01 This section covers the detailed methods to be followed in making transmission tests on verification trunks incoming to a step-by-step office from manual "A" and toll switchboards and from connector terminals.

1.02 Information covered in this section of practices is outlined in the following table:

Subject	Page
1. General	
2. Incoming Automatic Verification Trunks From Manual "A" and Toll Switchboards	
3. Incoming Verification Trunks From Toll Switchboards	
4. Incoming Verification Trunks From Connector Terminals	

1.03 Reference should be made to Section K20.01 for general testing methods and to Section K20.11 for general testing apparatus requirements.

2. INCOMING AUTOMATIC VERIFICATION TRUNKS FROM MANUAL "A" AND TOLL SWITCHBOARDS

2.01 These circuits are tested at the step-by-step "A" switchboard and are looped at the Manual "A" switchboard by means of a switchboard cord circuit or at the toll switchboard by means of a toll cord circuit. The testing procedure to be followed is the same as for "Outgoing Trunks to Manual Common Battery Switchboards. (Arranged for Ringdown Operation)," the method for which is outlined in Section K23.90, paragraphs 2.20 to 2.36, inclusive.

3. INCOMING VERIFICATION TRUNKS FROM TOLL SWITCHBOARDS

3.01 These trunk circuits terminate on the toll switchboard in jacks and at the step-by-step office in local selectors, A-B transmission selectors, toll transmission selectors or test distributors.

3.02 **Where the circuits terminate at the step-by-step office in local selectors,** the testing procedure to be followed is the same as for "Dial Trunks Incoming from Manual Toll Office Switchboards," as outlined in Section K23.23, paragraphs 2.01 to 2.20, inclusive except that local connector circuits instead of toll connector circuits will be involved in the tests.

3.03 **Where the circuits terminate at the step-by-step office in A-B transmission selectors or toll transmission selectors,** the testing procedure to be followed is the same as for "Dial Trunks Incoming from Manual Toll Office Switchboards," as outlined in Section K23.23, paragraphs 2.01 to 2.20, inclusive.

3.04 **Where the circuits terminate at the step-by-step office in test distributors,** the testing procedure to be followed is the same as for "Outgoing Verification Trunks to Test Distributors," as outlined in Section K23.96, paragraphs 2.01 to 2.21, inclusive.

4. INCOMING VERIFICATION OR OFFICIAL P.B.X. TRUNKS FROM CONNECTOR TERMINALS

4.01 These circuits are tested in the same manner as "Special Service Trunks to Centralized "A" Switchboards," the method for which is outlined in Section K23.50, paragraphs 2.01 to 2.24, inclusive.