




# HP 10 2101 Microphone Replacement

Follow this guide to replace the HP 10 2101 J6F00UA microphone. The replacement part number is 756038-001, and requires soldering to replace.

Written By: Bryce Harmsen



## INTRODUCTION

The microphone is soldered into the motherboard. This guide requires a knowledge of soldering. The back panel must be removed to access the microphone.

### TOOLS:

- [iFixit Opening Tools](#) (1)
- [Soldering Iron](#) (1)

## Step 1 — Back Panel



- Identify the SD card port.

## Step 2



- Insert the smallest plastic opening tool into the SD card port. Gently pry until the back panel separates from the screen panel.

**⚠ Do not insert opening tool too far.**  
Avoid making contact with the metal inside the port.

## Step 3




- Slide the opening tool along the seam between the back panel and the screen panel, prying the panels apart as you move around the edges.

## Step 4




- Separate the back panel from the rest of the device.

## Step 5 — Microphone



- Desolder the microphone wires from the motherboard.

## Step 6



- Separate the microphone from the rest of the device.

To reassemble your device, follow these instructions in reverse order.